







mining

fire protection

municipal

water conservation

food & beverage



## **SBS<sup>®</sup> Liquid Storage Tank Data Sheet**

WALL STRUCTURE

Zincalume® steel panels 0.8-3.88mm total gauge thickness conforming to SANS 9364 (ISO9364) and profiled to **SBS Tanks**® unique design.

**STEEL GRADE** 

G300 Zincalume®.

PROTECTIVE COATING

Zincalume® (Zinc/Aluminium Alloy), AZ 150 heavy duty coating. Additional coatings available to meet varying environmental

conditions and applications.

**COLOUR RANGE** 

Mill finish - silver. All standard tanks can be painted with approved

primers and paints. Range of colours available on request.

**ESTIMATED LIFE** 

60+ Years under normal climate and operational conditions.

LINER

Multi-layer woven PVC **SBS**° 700g. Tested to AS/NZS 4020-2005:

Testing Of Products For The Use In Contact With Drinking Water. Storage of various other liquids - Contact **SBS**\* for further details.

**BOLT SPECIFICATIONS** 

Proprietary **SBS**° bolt design M10 & M12 with serrated flange head. Hot dipped galvanized to SANS 121:2011 ISO 1461:2009. All

bolts are high tensile 8.8 grade. Bolt test certifications available

on request.

DOME ROOF

Zincalume® steel corrugrated sheets 0.47mm thick. G550 high

tensile grade with AZ150 coating. All trusses are hot dipped galvanized after fabrication. Clear span self-supporting roof with

no center post.

**OUTLETS/INLETS** 

All fittings/nozzles are manufactured from mild steel and hot dipped

galvanized to SANS 121:2011 ISO 1461:2009 after fabrication.

**GUARANTEE** 

Stainless steel and HDPE fittings are available on request.

SBS Tanks° carry an industry standard 12 month workmanship and

materials guarantee and a 10 year non-leak warranty is applicable provided the tank is installed by an approved **SBS**° installer.

typically 3-8 weeks ex factory, quantity and model dependant.

**MANUFACTURING TIME** 

Standard range, ex stock, immediately available. Non stock items

Typically 6-8 weeks ex factory.

DELIVERY TIME
INSTALLATION TIME

Typically - 1 day ST05/02 20kl (on site work time)

- 3 days ST18/02 250kl (on site work time)

- 15 to 17 days ST31/09 3.3ML (on site work time)

SITE PREPARATIONS

Level site capable of supporting a 100kPa with sand bed or

concrete ring beam as required. Site preparations to be arranged by client in accordance with engineers recommendations prior

to installation of SBS Tanks.









